

INDEX OF DRAWINGS

- A1 Cover and Index
- A2 Schedules and Notes
- A3 Spec Notes, Code Summary
- A4 Bldg. G Overall First Floor Plan
- A5 Bldg. G Overall Second Floor Plan
- A6 Bldg. G Enlarged First Floor Plan Units 1, 2, 3
- A7 Bldg. G Enlarged First Floor Plan Unit 4
- A8 Bldg. G Enlarged Second Floor Plan
- A9 Bldg. G Roof Plan
- A10 Bldg. G East and South Elevations
- A11 Bldg. G West and North Elevations
- A12 Bldg. G Building Section A--A
- A13 Bldg. G Building Section B--B
- A14 Bldg. G Building Section C--C
- A15 Bldg. G Building Section D--D
- A16 Bldg. G Building Section E--E
- A18 Details
- A19 Details
- A20 Details
  
- S1 Structural General Notes
- S2 Bldg. G Foundation Plan
- S3 Bldg. G First Floor Shear Wall Plan
- S4 Bldg. G Second Floor Shear Wall Plan
- S5 Bldg. G First Floor Framing Plan
- S6 Bldg. G Second Floor/Low Roof Framing Plan
- S7 Bldg. G High Roof Framing Plan
- S8 Details
- S9 Details

**baxter**  
**fourplexes**  
PHASE II  
BUILDING G

Owner/Contractor:  
Cook Inlet Housing Authority  
3510 Spenard Rd., Suite 100  
Anchorage, AK 99503

Structural Engineer:  
LDR Engineering Services, Inc.  
L.D. "Randy" Randolph  
(907) 227-0028

Designer:  
FRAME  
Clark Yerrington  
(907) 351-4805

APPLICABLE CODES  
2018 IRC and 2018 IBC with  
Municipal amendments.

GENERAL NOTES

1. Notify Designer of any errors or discrepancies in the documents.
2. Keep the job site clean and safe. Install temporary railings at level changes.
3. Provide a portable toilet for use during construction.
4. Consult Subcontractors to identify additional work items not specifically described herein.
5. All walls greater than 10'-0" height, provide fire blocking at 10'-0" maximum spacing.

COOK INLET HOUSING AUTHORITY  
BAXTER MULTIFLEXES, PHASE II  
Tract B, Valieskaya Addition No. 1  
NHN, ERMA COURT  
ANCHORAGE, ALASKA

**ROOM FINISH SCHEDULE NOTES**

1. Walls and ceilings shall be painted gypsum board, typical.
2. Substitute cementitious tile backer board for gypsum board at kitchen/laundry back splash walls and tub/showers where ceramic wall tile occurs (if applicable).

**WINDOW SCHEDULE GENERAL NOTES**

1. Sizes in Window Schedule are rough openings. Confirm frame size required with manufacturer, to allow for required insulation and sill space.
2. Normal head height is aligned with adjacent tops of doors, +/- 6-10" rough opening height (confirm).

**WINDOW SCHEDULE NOTES**

1. Vinyl frame windows shall be high quality residential grade with insulated double glazing, low E and argon. Frame color, white. Provide screens at operating windows.
2. Meet all applicable requirements for sleeping room egress, including min. 5.7 square feet net clear opening area; 24 inch min. net clear height; 20 inch min. net clear width (R310.2.1); max. 44 inch sill height (R310.2.2) and operating hardware complying with R310.1.1.
3. Translucent or patterned glass for privacy.

**DOOR SCHEDULE NOTES**

1. Weatherstripping and threshold.
2. Polished nickel hardware finish at bathroom set for bathroom use.
3. Door bottom gasket; brush seal at head and jambs; furnished will all necessary hardware and accessories including track, spring or other counterbalance mechanism, opener, sensors, wall button, remotes, key lock. Thermacore, model 495 with flush wood grain panel finish, manufactured by Overhead Door, color as selected -- or approved substitution.
4. 20-minute rated door/frame with weatherstripping, smoke/vapor seal, threshold and closer.
5. Entry door in wood frame with integral full-height safety glass side lite as shown on floor plans.
6. Confirm rough opening required. Flush panel door and plain rectangular side lite.

**WINDOW SCHEDULE BUILDING G**

	width	height	head ht.	operation	frame	glazing
A	3'-0"	5'-0"	normal	single-hung	vinyl	clear safety
B	3'-0"	5'-0"	normal	single-hung	vinyl	clear
C	3'-0"	4'-0"	normal	fixed	vinyl	clear
D	3'-0"	4'-0"	normal	single-hung	vinyl	clear
E	2'-0"	4'-0"	normal	fixed	vinyl	clear
F	6'-0"	4'-0"	normal	horiz. slider	vinyl	clear safety
G	4'-0"	2'-0"	normal	fixed	vinyl	clear
H	6'-0"	4'-0"	normal	horiz. slider	vinyl	clear safety
J	6'-0"	5'-0"	normal	fixed	vinyl	clear
K	3'-0"	4'-0"	normal	single-hung	vinyl	clear
L	3'-0"	4'-0"	normal	single-hung	vinyl	clear
M	3'-0"	4'-0"	normal	single-hung	vinyl	clear
N	3'-0"	5'-0"	normal	single-hung	vinyl	clear safety
P	3'-0"	5'-0"	normal	single-hung	vinyl	clear
R	3'-0"	5'-0"	normal	single-hung	vinyl	clear
S	4'-0"	4'-0"	normal	horiz. slider	vinyl	clear
T	5'-0"	4'-0"	normal	fixed	vinyl	clear
U	5'-0"	4'-0"	normal	fixed	vinyl	clear
V	4'-0"	4'-0"	normal	horiz. slider	vinyl	clear
W	5'-0"	4'-0"	normal	horiz. slider	vinyl	clear
X	5'-0"	2'-0"	normal	fixed	vinyl	clear
Y	5'-0"	4'-0"	normal	horiz. slider	vinyl	clear
Z	3'-0"	4'-0"	normal	fixed	vinyl	clear
AA	5'-0"	4'-0"	normal	fixed	vinyl	clear
BB	5'-0"	4'-0"	normal	horiz. slider	vinyl	clear
CC	3'-0"	4'-0"	normal	single-hung	vinyl	clear
DD	5'-0"	4'-0"	normal	horiz. slider	vinyl	clear
EE	5'-0"	4'-0"	normal	fixed	vinyl	clear
FF	6'-0"	4'-0"	normal	horiz. slider	vinyl	clear
GG	6'-0"	4'-0"	normal	horiz. slider	vinyl	clear

COOK INLET HOUSING AUTHORITY  
BAXTER MULTIFLEX, PHASE II  
Tract B, Valdez, Alaska Addition No. 1  
NHN, Ertha Court  
ANCHORAGE, ALASKA

**DOOR SCHEDULE 3-BR END UNIT (G1)**

	width	height	type	material	finish	hardware	glazing	notes
100	2'-8"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	none	1
101	2'-8"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	none	1
102	3'-0"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	none	1, 5
103	2'-8"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	none	1, 6
104	2'-8"	6'-8"	one pnl.	wood	clear	latchset	none	2
105	2'-8"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
106	2'-8"	6'-8"	one pnl.	wood	clear	trolley trk./pull	none	2
107	4'-0"	6'-8"	one pnl.	wood	clear	latchset	none	2
108	[NOT USED]							
109	[NOT USED]							
201	2'-8"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
202	2'-8"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
203	2'-8"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
204	2'-4"	6'-8"	one pnl.	wood	clear	latchset	none	2
205	2'-4"	6'-8"	one pnl.	wood	clear	latchset	none	2
206	2'-4"	6'-8"	one pnl.	wood	clear	latchset	none	2
207	5'-0"	6'-8"	one pnl.	wood	clear	track and pulls	none	2
208	5'-0"	6'-8"	one pnl.	wood	clear	track and pulls	none	2
209	[NOT USED]							

**2-BR UNIT (G2, G3)**

	width	height	type	material	finish	hardware	glazing	notes
110	2'-8"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	none	1
111	3'-0"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	none	1, 5
112	2'-8"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	safety	1, 6
114	2'-4"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
115	2'-8"	6'-8"	one pnl.	wood	clear	trolley trk./pull	none	2
116	2'-0"	6'-8"	one pnl.	wood	clear	latchset	none	2
117	[NOT USED]							
210	2'-8"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
211	2'-8"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
212	2'-4"	6'-8"	one pnl.	wood	clear	latchset	none	2
214	2'-4"	6'-8"	one pnl.	wood	clear	latchset	none	2
215	3'-0"	6'-8"	one pnl.	wood	clear	latchset	none	2
216	1'-6"	6'-8"	one pnl.	wood	clear	latchset	none	2
217	5'-0"	6'-8"	one pnl.	wood	clear	track and pulls	none	2
218	[NOT USED]							
219	[NOT USED]							

**2-BR ACCESSIBLE UNIT (G4)**

	width	height	type	material	finish	hardware	glazing	notes
141	2'-8"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	none	1
142	3'-0"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	none	1, 5
143	3'-0"	6'-8"	exterior	fiberglass	paint	lockset/dbolt	none	1
144	3'-0"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
145	2'-8"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
146	3'-0"	6'-8"	one pnl.	wood	clear	privacy lock	none	2
147	3'-0"	6'-8"	one pnl.	wood	clear	latchset	none	2
148	1'-6"	6'-8"	one pnl.	wood	clear	latchset	none	2
149	5'-0"	6'-8"	one pnl.	wood	clear	track and pulls	none	2
150	5'-0"	6'-8"	one pnl.	wood	clear	track and pulls	none	2
151	3'-0"	6'-8"	one pnl.	wood	clear	trolley trk./pull	none	2

**AREA SUMMARY**

UNIT G1 -- 3-BR 2-BR	564 SQ. FT.
FIRST FLOOR -- LIV. AREA	666
SECOND FLOOR -- LIV. AREA	666
SUBTOTAL LIVING AREA	1,220
FLEX	31
UNIT TOTAL	1,261

UNIT G2 -- 2-BR 1.5-BR	444 SQ. FT.
FIRST FLOOR -- LIV. AREA	487
SECOND FLOOR -- LIV. AREA	487
SUBTOTAL LIVING AREA	931
FLEX	46
UNIT TOTAL	977

UNIT G3 -- 2-BR 1.5-BR	444 SQ. FT.
FIRST FLOOR -- LIV. AREA	487
SECOND FLOOR -- LIV. AREA	487
SUBTOTAL LIVING AREA	931
FLEX	46
UNIT TOTAL	977

UNIT G4 -- 2-BR 1-BR	924 SQ. FT.
FIRST FLOOR -- LIV. AREA	924
SECOND FLOOR -- LIV. AREA	924
SUBTOTAL LIVING AREA	1,848
FLEX	42
UNIT TOTAL	1,890

BUILDING GRAND TOTAL	4,191 SQ. FT.
STAIRS COUNTED AT FIRST FLOOR ONLY, TYP.	
PARKING EXCLUDED, TYP.	

#### EXCAVATION AND FILL

Slope finish grade away from buildings 6 inches minimum for a distance of 10'-0".  
Place any large rocks unearthened during excavation near the driveway.

#### SITE UTILITIES

Connect water service line to water main.  
Connect drain lines to sanitary sewer main.  
Provide natural gas service entrance and meter.  
Provide 200 amp electrical service entrance and meter.  
Provide service entrance for Cable TV/Internet.

#### SITE WORK AND LANDSCAPING

Preserve existing natural vegetation to the extent possible.  
Provide house numbers and unit numbers as shown on Elevations.

#### HEATING

Design of the heating and ventilation systems shall be by Contractor.  
Permits shall be acquired and paid for by the Contractor.  
Inspections shall be scheduled by the Contractor and/or Subcontractor.  
Provide natural gas fired furnace for each living unit, with minimum output of 50 Btu/h per square foot of area served.  
Locate mechanical equipment in Shared Mechanical Room.

#### ELECTRICAL

Design of the electrical systems shall be by Contractor.  
Permits shall be acquired and paid for by the Contractor.  
Inspections shall be scheduled by the Contractor and/or Subcontractor.  
Rough in all boxes and conduct a walk-through review of the locations of all power outlets, switches, light fixtures and any other electrical items with Owner prior to wiring.  
Provide concealed Cable TV/Internet wiring and wall boxes from service entrance to locations indicated on Floor Plan.  
Switched outlets shall be half switched.

Confirm power requirements for all Owner-furnished items.  
Provide smoke detectors in each bedroom and on each floor level at high point of ceiling. Provide carbon monoxide detector on each level. Detectors shall be hardwired in a series, so if one sounds they all do, with battery backup.  
Provide hardwired doorbell at main entry doors; locate chimes in hallway close to bottom of stairs.

#### SIDING

Install all siding over air infiltration retarder.  
Provide a sample of each type of siding to be used prior to installation or ordering of materials.  
Provide siding types as shown on Elevations.  
Provide all necessary trim, flashing, terminations and accessories, whether shown/noted or not.

#### EXTERIOR TRIM

Provide 2x8 cedar fascia, or fiber cement plank same dimension.  
Provide window trim, corner trim and other trim as shown/noted.

#### INSULATION

Provide foundation insulation as shown/noted in Sections and details.  
Provide minimum R-20 insulation at foundation walls.  
Provide minimum R-21 insulation, batt or blown-in cellulose at exterior walls.  
Provide minimum R-38 insulation, foam in place at rim joint.  
Provide minimum R-49 insulation, batt or blown-in cellulose at roofs, with minimum 2" vent space above.  
Provide minimum R-38 insulation, foam in place at floor cantilevers.  
Provide bird screen and insect screen at vent openings.  
Vent area shall be equivalent to 1/150th of roof area, 50% at each side at end walls.  
Provide 6-mil vapor retarder at warm side of all wall and roof insulation.  
ATTIC VENTILATION  
See Insulation section.

#### ROOFING

Provide asphalt composition shingles over ice and water shield (self-adhering modified bitumen membrane).  
Provide continuous embedded edge metal flashing at roof edges.  
Provide gutter and downspout/s according to best standard local practice.  
Locate downspout outlets 5'-0" beyond exterior wall.

#### DRYWALL AND PAINT

Provide 1/2" gypsum board at walls.  
Provide 5/8" gypsum board at ceilings.  
Provide samples of wall texture and paint/stain color samples, prior to commencement of work or ordering of materials.  
Provide exterior grade primer and paint at any siding types not supplied by manufacturer, and exterior soffit and fascia.  
Provide exterior-grade stain at exposed truss tails and underside of sheathing.  
Provide primer and two coats of water based latex enamel at interior.

#### INTERIOR TRIM

Typical base trim and door trim shall be rectangular MDF or 4" rubber base as selected. Prime and paint MDF with two coats semi-gloss, color to match adjacent walls.  
Window trim shall be min. 3/4" rectangular clear hem-fir, poplar or MDF sill with gypsum board returns at jams and head. Gypsum board returns four sides OK for high windows.

#### CRAWL SPACE VENTILATION

Crawl spaces shall be mechanically ventilated.  
Provide constant velocity fan with 1 CFM per square foot of crawl space footprint.  
Transfer grilles, floor openings located opposite of fan/dischARGE to pull air across crawl space.  
Design and installation by Contractor.  
Comply with IRC-408.3, 2.1.

#### BUILDING CODE SUMMARY

International Residential Code, 2018 edition

Use -- two family dwelling R101.2

Allowable number of stories -- 3

Actual number of stories -- 2

Exterior walls are not required to be fire rated, min. 5'-0" fire separation at property line. Table R202.1(1)

Smoke alarms are required. R314

Address identifying signage is required. R319

Minimum stairway width, 36". R311.7.1

Stairway maximum riser height, 7-3/4"; minimum tread depth, 10". R311.7.5.1, R311.7.5.2

Handrails -- one side of stair runs only. Handrails are not required at stair flights with three or fewer risers. R311.7.8

Handrail height -- 34" above nosings, except at transitions as allowed by R311.7.8.1, exception 2.

Guard height -- minimum 34" above stair nosings. R312.1.2, exception 1

Guard height -- minimum 36" at deck railing and any other locations not along stair runs. R312.1.1

#### ZONING CODE SUMMARY

Title 21, Anchorage Municipal Code

Zoning district: R-3

Property area: 47,418 sq. ft.


Lot coverage, allowed: 40% (multifamily); 60% (lowhouse)

Table 21.06-1

Lot coverage, proposed: 49.3%

Height, allowed: 35 ft. Table 21.06-1


Height, proposed: 23 ft.



COOK INLET HOUSING AUTHORITY  
BAXTER MULTIFLEXES, PHASE II  
Tract B, Valetskaya Addition No. 1  
NNN, Extra COURT  
ANCHORAGE, ALASKA




BUILDING G  
Overall  
First Floor Plan



BUILDING C  
Overall  
Second Floor Plan

COOK INLET HOUSING AUTHORITY  
BAXTER MULTIFLEXES, PHASE II  
Tract B, Valetskaya Addition No. 1  
NHV, Erma COURT  
ANCHORAGE, ALASKA



ROOF DESIGN ZONES  
SEE ROOF DESIGN TABLE ON S1  
LOWER ROOFS  
INDICATED HATCHED  
UPPER ROOFS  
ZONE 1

NOTES

1. ALL ASPHALT COMPOSITION SHINGLES SHALL BE INSTALLED OVER BITUMEN MEMBRANE. CONTINGUOUS, SELF-ADHERING REQUIRED.

LEGEND

INDICATES DIRECTION OF DOWNWARD SLOPE  
ROOF PITCH, 3 IN 12




BUILDING G  
Roof Plan

COOK INLET HOUSING AUTHORITY  
BAXTER MULTIFLEXES, PHASE II  
Tract B, Valetskaya Addition No. 1  
NHV, Erta Court  
ANCHORAGE, ALASKA












**Roof Transition**  
SEE DTL 5/29 FOR  
ADDITIONAL INFORMATION




**Typical Stair Handrail**  
SEE DTL 5/29 FOR  
ADDITIONAL INFORMATION




**Ridge/Headwall**  
SEE DTL 11/29 FOR  
ADDITIONAL INFORMATION




**Typical Rake**  
SEE DTL 12/29 FOR  
ADDITIONAL INFORMATION




**Eave**  
SEE DTL 12/29 FOR  
ADDITIONAL INFORMATION




**Back Porch Canopy Roof**  
SEE DTL 5/29 FOR  
ADDITIONAL INFORMATION




**Eave**  
SEE DTL 12/29 FOR  
ADDITIONAL INFORMATION




**Roof Transition**  
SEE DTL 2/29 FOR  
ADDITIONAL INFORMATION




**Eave**  
SEE DTL 12/29 FOR  
ADDITIONAL INFORMATION




**Eave**  
SEE DTL 12/29 FOR  
ADDITIONAL INFORMATION



**Eave**  
SEE DTL 12/29 FOR  
ADDITIONAL INFORMATION



**Eave**  
SEE DTL 12/29 FOR  
ADDITIONAL INFORMATION



**Eave**  
SEE DTL 12/29 FOR  
ADDITIONAL INFORMATION

